STATEMENT OF WORK Vegetative Barrier (601) Michigan

These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific Statements of Work.

DESIGN

Deliverables:

- 1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. List of facilitating practices (e.g. Residue Management, Mulch Till, Residue Management, No Till/Strip Till, Contour Farming)
 - d. Practice standard criteria-related inventories and analyses to develop design and specifications including, but not limited to:
 - i. Adapted species
 - ii. Number of rows and species within designed rows
 - iii. Planting method, timing, and spacing (within and between rows)
 - iv. Cultural practices
- 2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describe the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements of conservation practice standard Vegetative Barrier (Code 601). Plan or job sheet and cost estimate prepared as required in electronic Field Office Technical Guide, Section IV, Vegetative Barrier Specification subsection.
- 3. Operation and maintenance plan.
- 4. Certification that the design meets practice standard criteria and complies with applicable laws and regulations.
- 5. Design modifications during installation as required.

INSTALLATION

Deliverables

- 1. Pre-application conference with client.
- 2. Verification that client has obtained required permits.
- 3. Staking and layout according to plans and specifications including applicable layout notes.
- 4. Species inspection.
- 5. Installation assistance as needed.
- 6. Application guidance as needed.
- 7. Facilitate and implement required design modifications with client and original designer.
- 8. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
- Certification that the application process and materials meet design and permit requirements per the NRCS National Vegetative Barrier Job Sheet or equivalent.

CHECK OUT

Deliverables

- 1. Records of application.
 - a. Extent of practice units applied
 - b. Actual materials used
- 2. Certification that the application meets NRCS standards and specifications and is in compliance with permits.
- 3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard Vegetative Barrier -601
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook
- NRCS CORE 4 Conservation Practices Reference Manual
- NRCS National Vegetative Barrier Job Sheet 601