

STATEMENT OF WORK
Channel Bank Vegetation (322)
New Mexico

The following deliverables are required for the complete implementation and documentation of this conservation practice. Section 4 of the New Mexico Technical Guide (NM eFOTG) should also be reviewed for additional practice-specific requirements and Design and Check Data Requirements where those have been developed. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN**Deliverables:**

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM part 503-Safety, Section 503.00 through 503.22)
 - d. List all required and/or facilitating practices
 - e. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - i. Channel side slopes
 - ii. Need for topsoil stockpiling
 - iii. Bank stabilization techniques
 - iv. Vegetative species selection
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Operation and maintenance plan
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations.
5. Design modifications during installation as required.

INSTALLATION**Deliverables**

1. Pre-installation conference with client.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation guidance as needed.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT**Deliverables**

1. Records of application.
 - a. Extent of practice units applied
 - b. Actual mitigation measures used
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits.
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard –Channel Bank Vegetation – 322.
- NRCS National Engineering Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook