

CONSTRUCTION SPECIFICATION

VA-711. REMOVAL OF WATER

1. **SCOPE**

The work shall consist of the removal of surface water and ground water as needed to perform the required construction.

2. **DIVERTING SURFACE WATER**

Protective measures needed to divert streamflow and other surface water shall be built, maintained and operated during construction.

3. **DEWATERING CONSTRUCTION AND BORROW SITES**

The construction site shall be dewatered and kept free of standing water or excessively muddy conditions as needed for proper execution of the construction work. Dewatering shall include furnishing, installing, operating and maintaining all equipment including such as pumps as needed.

4. **REMOVAL OF TEMPORARY WORKS**

After the temporary works have served their purposes or prior to the Contractor leaving the site, they shall be removed or graded to present a sightly appearance without interfering with permanent drainage systems or stream flows.

5. **EROSION AND POLLUTION CONTROL**

All temporary works shall be accomplished in such a manner that erosion and the transmission of sediment and other pollutants are minimized.