

WISCONSIN CONSTRUCTION SPECIFICATION

5. CONSTRUCTION SITE POLLUTION CONTROL

1. SCOPE

The work shall consist of installing measures or performing work to control erosion and minimize the production of sediment and other pollutants to water and air from construction activities.

2. MEASURES

Erosion and sediment control measures and works shall be installed to prevent or minimize sediment production and transport offsite. The measures and works shall include, but are not limited to, the following:

- a. Diversions - Divert water from work areas and collect water from work areas for treatment and safe disposition. Temporary diversions shall be removed and the area restored to its near original condition when the diversions are no longer required or when permanent measures are installed.
- b. In-Channel Sediment Control - Sediment produced within the stream channel during construction will be retained in the work area. Sediment retention will be accomplished by using a temporary, excavated sediment trap and/or a barrier constructed of geotextile and hay bales. Turbid water in the retention area may be pumped to a well-vegetated area away from the stream. The vegetation will serve to filter the sediments before the flow returns to the stream. Discharge areas from all pump hoses shall be stabilized. At no time shall the pump discharge be allowed to cause erosion at the discharge point.
- c. Mulching - Mulch provides temporary protection of the soil surface from erosion. The method of application is specified on the construction drawings
- d. Sediment Basins - Sediment basins collect, settle, and eliminate sediment from eroding areas from impacting properties and streams below the construction site(s). These basins are temporary and shall be removed and the area restored to its original condition when they are no longer required or when permanent measures are installed.
- e. Sediment Filters - Straw bale filters or geotextile sediment fences (silt fence) trap sediment from areas of limited runoff. Sediment filters shall be properly anchored to prevent erosion under or around them. These filters are temporary and shall be removed and the area restored to its original condition when they are no longer required or when permanent measures are installed. The method is shown on the construction drawings.
- f. Seeding - Seeding to protect disturbed areas shall occur as soon as reasonably possible following completion of that earthwork activity. All seeding operations shall be performed in such a manner that the seeds are applied in the specified quantities

uniformly in the designated areas. The method and rate of seed application are specified on the construction drawings

- g. Silt Curtain or Turbidity Barrier - Silt Curtain and Turbidity Barriers can be used to minimize the transport of sediment from an area where construction activities are occurring within or directly adjacent to a waterway or waterbody. The fabric shall be removed after the construction activities have ceased and the sediment has settled. Care should be taken to prevent the re-suspension of sediment during removal.
- h. Staging of Earthwork Activities - The excavation and moving of soil materials shall be staged to minimize the area disturbed and the time these locations are vulnerable to erosion.
- i. Stockpiling Material - The stockpiled materials shall be protected from concentrated flows and/or flooding, to minimize sediment movement offsite.
- j. Stream Crossings - Culverts or bridges should be used where equipment crosses streams. They are temporary and shall be removed and the area restored to its near original condition when the crossings are no longer required or when permanent measures are installed.
- k. Waterways - Waterways shall be used to safely dispose of runoff from fields, diversions, and other structures or measures. These works are temporary and shall be removed and the area restored to its original condition when they are no longer required or when permanent measures are installed.
- l. It is the responsibility of the contractor or their designee for the cleanup or removal of sediment transported offsite due to failure to maintain erosion control measures during all phases of the construction.

3. CHEMICAL POLLUTION

The contractor shall safely dispose of chemical pollutants (such as drained lubricating or transmission fluids, grease, soaps, concrete mixer washwater, or asphalt, produced as a byproduct of the construction activities) off site. The contractor is responsible for reporting and clean up of all accidental spills and leaks.

In the event a piece of equipment develops a leak during the construction work, the leak shall be repaired before work continues. All excess fluids will be cleaned from the machine prior to its return to the work area.

If a leak occurs when equipment is working in or near a waterbody, the machine shall be immediately moved a safe distance away from the waterbody.

4. AIR POLLUTION

The burning of brush or slash and the disposal of other materials shall adhere to state and local regulations.

Fire prevention measures shall be taken to prevent the start or spreading of wildfires that may result from project activities. Firebreaks or guards shall be constructed and maintained.

All public access or haul roads used by the contractor during construction of the project shall be treated to fully suppress dust. All dust control methods shall ensure safe construction operations at all times. If chemical dust suppressants are applied, the material shall be a commercially available product specifically designed for dust suppression and the application shall follow manufacturer's requirements and recommendations. A copy of the product data sheet and manufacturer's recommended application procedures shall be provided to the technician before the first application.

5. MAINTENANCE, REMOVAL, AND RESTORATION

All pollution control measures and temporary works shall be adequately maintained in a functional condition for the duration of the construction period. All temporary measures shall be removed and the site restored to near original condition.

All equipment used within the construction site shall be well maintained. All equipment lines and fittings shall be checked on a daily basis to ensure that they are in good working order.