

NATURAL RESOURCES CONSERVATION SERVICE
Wyoming
CONSTRUCTION SPECIFICATIONS
FOR
BEDDING

(Owner/Operator)

(Project Title)

GENERAL

Installation shall be in accordance with an approved design and plan. Details of construction shown on the drawings but not included herein are considered as a part of this specification. Construction activities shall be in accordance with applicable OSHA regulations.

ADDITIONAL SPECIFICATIONS

SITE PREPARATION

The area to be bedded shall be cleared and stripped of all brush, roots, sod, large rock or other material not suited for making a compacted earthfill.

CHANNELS

Channels shall be excavated to the lines and grades as shown on the drawings or as staked in the field. The finished cross-section shall have a smooth surface.

RIDGE FILLS

The thickness of layers prior to compaction shall not be more than 8 inches in thickness. Compaction shall be no less than two passes of pneumatically tired equipment over the entire surface of each lift.