

NATURAL RESOURCES CONSERVATION SERVICE
Wyoming
CONSTRUCTION SPECIFICATIONS
FOR
CLEARING AND SNAGGING

(Owner/Operator)

(Project Title)

GENERAL

Installation shall be in accordance with an approved design and plan. Details of construction shown on the drawings but not included herein are considered as a part of this specification. Construction activities shall be in accordance with applicable OSHA regulations.

PERMITS

The landowner is responsible for obtaining necessary local, State and Federal permits.

CLEARING

All designated trees, stumps, logs and brush within the designated areas shown on the drawings and marked in the field shall be removed and placed as specified on the drawings. When the removal of vegetative top growth is specified, care shall be taken to prevent excess damage to plant roots.

Trees designated for felling shall be removed in a manner as to avoid damage to other trees and items noted as not to be disturbed.

SNAGGING

Gravel/sediment bar removal shall be limited to that specified on the drawings. Unless otherwise specified gravel/sediment work shall be above the level of the water.

All gravel/sediment bar removal shall be in accordance with State of Idaho "Stream Alteration, Rules and Guidelines and Minimum Standards" unless waived in writing.

EXCAVATION

Gravel/sediment bars shall be shaped to the lines and grades shown on the drawings.

MATERIAL DISPOSAL

Materials from the clearing and snagging operations shall be salvaged and used as specified on the drawings. Waste and spoil materials and those in excess of needs for other work components shall be placed in the designated waste disposal areas. Waste disposal areas will be shaped and smoothed. All burning shall be in accordance with local, County and State regulations.

ADDITIONAL SPECIFICATIONS