

NATURAL RESOURCES CONSERVATION SERVICE
Wyoming
CONSTRUCTION SPECIFICATIONS
FOR
DRAINAGE WATER MANAGEMENT

(Owner/Operator)

(Project/Title)

GENERAL

Installation shall be in accordance with a design and plan approved by the responsible technician. Details of construction shown in the design and plan but not included here shall be considered as a part of this specification. Construction activities shall be in accordance with applicable OSHA regulations and stream channel alteration permits.

and unless otherwise noted and shall be removed when they are no longer needed. Excavation for dewatering bypass channels shall proceed from the downstream end.

Disturbed areas and designated critical areas will be treated as specified in the ADDITIONAL SPECIFICATIONS or as noted on the drawings.

INSTALLATION

The system components shall be of the type, materials, size and shall be constructed to the lines, grades as shown on the drawings and/or staked in the field. The individual system component materials and installation shall meet the requirements of Wyoming Construction Specification(s) or other specification(s) as listed on the drawings or in the ADDITIONAL SPECIFICATIONS.

The clearing and grubbing of vegetation shall be limited to that needed to construct the system. Any vegetation specifically designated for saving shall not be disturbed. When specific ingress/egress access routes and/or construction limits are defined the construction operations shall be limited to the designated areas.

All equipment shall be maintained and fueled away from the edge of wetlands. Temporary measures shall be installed to prevent accidental spills from entering water bodies. Cleanup of spills shall be in accordance with applicable Federal, State, local rules/regulations.

All measures installed for dewatering the site and/or the trapping of sediment from the construction area shall be considered temporary

ADDITIONAL SPECIFICATIONS