

NATURAL RESOURCES CONSERVATION SERVICE
Wyoming
CONSTRUCTION SPECIFICATIONS
FOR
OBSTRUCTION REMOVAL

(Owner/Operator)

(Project/Title)

GENERAL

Obstruction removal shall be in accordance with a plan approved by the responsible technician. Details of removal and/or disposal shown in the plan but not included herein shall be considered as a part of this specification. All activities shall be in accordance with applicable OSHA regulations.

other structures shall be broken into pieces suitable for hauling and disposal.

When no disposal site is designated, the Contractor shall be responsible for removing all materials from the site and finding an off site disposal area. Such disposal shall be in conformance with State and local laws and regulations.

REMOVAL

All structures, fences, trees, stumps, boulders, etc. designated for removal shall be removed within the areas and to the depths as defined on the drawings or as described in the ADDITIONAL SPECIFICATIONS.

ADDITIONAL SPECIFICATIONS

SALVAGE

Structures, structure parts, pipes, fence materials, etc. that are designated for salvage shall be carefully removed and stockpiled/stacked in designated areas. Fence wire shall be neatly rolled into uniform rolls and piled with posts, unless otherwise specified.

DISPOSAL

When on site disposal areas are shown or described on the plans the Contractor shall bury or burn the materials designated for on site disposal as directed by the landowner and in conformance with local laws and ordinances. All burning shall be in conformance with State and local laws and regulations. Materials designated for burial shall be covered with a minimum of 2 feet of soil. The hole shall be deep enough to allow burial and placement of the soil cover surface at or near original elevation of the soil surface. Concrete slabs and