

NATURAL RESOURCES CONSERVATION SERVICE
Wyoming
CONSTRUCTION SPECIFICATIONS
FOR
SPOIL SPREADING

(Owner/Operator)

(Project Title)

GENERAL

Installation shall be in accordance with an approved design and plan. Details of construction shown on the drawings but not included herein are considered as a part of this specification. Construction activities shall be in accordance with applicable OSHA regulations.

ADDITIONAL SPECIFICATIONS

SITE PREPARATION

Where clearing of the spoil disposal area is specified on the drawings the designated area(s) shall be cleared and stripped of all brush, roots, sod, large rock or other material not suited for making a compacted earthfill.

FILLS

The thickness of layers requiring compaction shall be placed in layers no more than 8 inches in thickness. Compaction shall be no less than two passes of pneumatically tired equipment over the entire surface of each lift.

Surfaces of compacted and uncompacted areas shall be smoothed.