STATEMENT OF WORK Windbreak/Shelterbelt Renovation (650) Wyoming

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

- 1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - Determination of needed cultural measures including addition of new rows to maintain intended density and functions
 - ii. Protective measures for plants to maintain intended functions including use exclusion
- 2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
- 3. Documentation of needed operation and maintenance.
- 4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations and Conservation Practice Work Sheet WY-ECS-78.
- 5. Design modifications during installation as required.

INSTALLATION

Deliverables

- 1. Pre-application conference with client.
- 2. Verification that client has obtained required permits.
- 3. Staking and layout according to plans and specifications including applicable layout notes.
- 4. Application guidance as needed.
- 5. Facilitate and implement required design modifications with client and original designer.
- 6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
- 7. Certification that the application process and materials meet design and permit requirements and Conservation Practice Work Sheet WY-ECS-78.

CHECK OUT

Deliverables

- 1. Records of application.
 - a. Extent of practice units applied
 - b. Actual cultural measures/plant materials used and applied
- 2. Certification that the application meets NRCS standards and specifications and is in compliance with permits and Conservation Practice Work Sheet WY-ECS-78.
- 3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard Windbreak/ Shelterbelt Renovation, 650
- NRCS National Forestry Handbook (NFH), Part 636.4 and Conservation Practice Work Sheet WY-ECS-78
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook

August 24, 2004 Page1 of 1